


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Trego County. Sec. 11 Twp. 12 Rge. 21 (E) (W)
Location as "NE/CNW/SW" or footage from lines. Gen. SW/4 NW/4 NW/4
Lease Owner Amerada Petroleum Corporation
Lease Name L. J. Schaefer Well No. 1
Office Address 614 Orpheum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 30 19 53
Application for plugging filed March 30 19 53
Application for plugging approved March 30 (verbally) 19 53
Plugging commenced March 30 19 53
Plugging completed March 30 19 53
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200'
Setplug at 200'
Dumped 1 sack cottonseed hulls on top of plug
Mixed and sumped 15 sacks cement
Filled hole with heavy mud to 40' below bottom of cellar; SET plug at 40'
Dumped 1/2 sack cottonseed hulls on top of plug
Mixed and dumped 10 sacks cement filling hole to top of 8-5/8" casing in bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Survey Drilling Company, c/o Roy Cook
Address Staatz Hotel, Wakeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. J. Stone (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. J. Stone
614 Orpheum Bldg., Wichita, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 53
[Signature]
Notary Public.

My commission expires October 4, 1956

PLUGGING
FILE SEC 11 T 12 R 2134
BOOK PAGE 88 LINE 58

24-2675-5 2-52-20M
APR 2 - 1953
CONSERVATION DIVISION
Wichita, Kansas

4-2-1953



DRILLER'S LOG

Company: Amerada Petroleum Corporation SW NW NW
 Sec. 11, Twp. 12S, Rge. 21W

Farm: L. J. Schaefer Well No. 1 County: Trego, Kansas
 Total Depth: 4022

Comm: 3-13-53 Comp: 3-29-53
 Contractor: Survey Drilling Company
 Casing: 8-5/8" - 212' - cemented

Elevation: 2326 Ground
 2334 Derrick Floor

Production: Dry

Figures below indicate bottom of formations

Surface Clay and Sand	0 -	150
Sand and Shale		150 - 1755
Anhydrite		1755 - 1800
Shale and Shells		1800 - 3399
Lime and Shale		3399 - 3593
Shale		3611
Lime and Shale		3627
Lime		3874
Shale		3920
Chert and Lime		3959
Cherty Conglomerate		3997
Dolomite		4022
Rotary Total Depth		4022

This is to certify that the above information is, to the best of our knowledge true and correct.

Amerada Petroleum Corporation

BY: Charles E. Terry

SUBSCRIBED AND SWORN to before me this 21st day of May, 1953.

J. P. Hendrick
 Notary Public

My commission expires Oct 4th 1956

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 26 1953
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

FILE SEC 11 T 12 R 21W
 BOOK PAGE 88 LINE 38