


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Trego County. Sec. 6 Twp. 11 Rge. (E) 24 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SW  
Lease Owner Murfin- Rains & Williamson  
Lease Name Berg Well No. 1  
Office Address 617 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-15 19 58  
Application for plugging filed 5-15 19 58  
Application for plugging approved 5-15 19 58  
Plugging commenced 5-15 19 58  
Plugging completed 5-15 19 58  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert P. Leiker, 805 Main Street, Victoria Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4020 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	208	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 540 feet displaced 20 sacks of cement through drill pipe. Set second plug at 180 feet displaced 20 sacks of cement through drill pipe. Set third plug at 40 feet displaced 1/2 sack of hulls and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Co.  
Address 617 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Murfin

~~(employee of owner)~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 19 58

My commission expires June 14, 1961

Phyllis Brown  
Phyllis Brown Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1958 6-7-1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 6 T. 11 R. 24  
BOOK PAGE 101 LINE 27

# WELL LOG

COMPANY **Murfin-Rains & Williamson**

SEC. 6 T. 11S R. 24W  
LOC. NW NW SW

FARM **Berg**

NO. **1**

TOTAL DEPTH **4020**

COMM. **4-29-58**


COMP. **5-15-58**

COUNTY **Trego**  
KANSAS

SHOT OR TREATED

CONTRACTOR **Murfin Drilling Co.**

ISSUED



CASING

20	10	
15	8	5/8" @ 208' w/ 75 sacks
12	6	
13	5	

ELEVATION **2401 KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS:

25	Surface Soil	Heebner	3728'
50	Rock & Sand	Toronto	3749
190	Clay - Shale	Lansing - Kansas City	3765
410	Shale	Base Kansas City	4002
785	Shale - Shells	Total Depth	4020
1095	Shale - Sand Shells		
1315	Shells - Shale		
1400	Shale - Hard Sand		
1575	Shale - Shells		
2035	Red Bed		
2075	Anhy		
2350	Shale - Shells		
3630	Shale - Lime		
4020	Lime		

RECEIVED  
COMMISSION

JUN 7 1953

REGISTRATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Sedgwick

ss:

PLUGGING  
FILE SEC 6 T. 11 S. 24W  
BOOK PAGE 101 LINE 27

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Berg # 1 well.

*W. R. Murfin*

Subscribed and sworn to before me this 6th day of June 19 58

My Commission Expires: June 14, 1961

*Phyllis Brown*  
Phyllis Brown NOTARY PUBLIC