

15.195.00181.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Trego County, Sec. 11 Twp. 11S Rge. 21 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from line 440' from S&440' from W line

Lease Owner Continental Oil Company

Lease Name H. C. Walz "A" Well No.

Office Address Drawer 1267, Ponca City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-30 19 51

Application for plugging filed 10-1 19 51

Application for plugging approved 10-4 19 51

Plugging commenced 10-1 19 51

Plugging completed 10-1 19 51

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, Telephone

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays Kansas

Producing formation Arbuckle Depth to top 3869' Bottom 3936' Total Depth of Well 3936' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Dry	3869'	3936'	10 3/4	2125'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 200'; set plug at 200' and cemented with 20 sacks; filled hole with heavy mud to 40' and capped with 15 sacks cement. Plugged and abandoned 10-1-51

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1951

Name of Plugging Contractor Anschutz Drilling Company

Address 709-10 Union National Bank Building

Wichita, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

F. L. Dunn (employee of owner) or (owner of operation) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. L. Dunn

R. F. D. #4, Lyons, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of Nov, 1951

A. E. Longmeyer
Notary Public.

My commission expires October 10, 1955

23-8390-s 6-51-20M

FLD-AEA-KJQ
State Corp. Comm.
TCD
File

PLUGGING
FILE SEC 11 T 11 R 21 W
BOOK PAGE 114 LINE 17

State

CONTINENTAL OIL COMPANY

#1 Walz "A" SW SW SW 11-115-21W
Trego County, Kansas

0	715	Shale & shells
715	850	Sand
850	1125	Shale & shells
1125	1340	White sand & red sand
1340	1550	Green & blue shale & red bed
1550	1620	Shale, red bed
1620	1680	Anhydrite
1680	2315	Shale & shells
2315	2540	Lime
2540	2655	Lime, shale
2740	2845	Lime
2845	2935	Lime, shale
2935	3000	Lime
3000	3295	Lime, shale
3225	3275	Lime
3275	3360	Shale, lime
3360	3590	Lime
3590	3625	K. C. Lime
3625	3770	Lime
3770	3805	Cong., chert
3805	3907	Cong.
3907	3939	Arb
	3939	Total Depth
		D&A

COMMENCED: 9/18/51
COMPLETED: 9/30/51

CASING RECORD

Set 10-3/4" surface casing @
212' with 175 sacks cement.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Walz "A" located SW SW SW 11-115-21W, Trego County, Kansas.

ANSCHUTZ DRILLING COMPANY

BY: *H. R. Jensen*

Subscribed and sworn to before me this 11th day of October, 1951.

Patricia Decker
Notary Public

My commission expires: January 21, 1954.

PLUGGING
FILE SEC 11 T 11 R 21W
BOOK PAGE 114 LINE 17

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1951
CONSERVATION DIVISION
Wichita, Kansas