

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW NW

SEC. 35 TWP. 14 RGE. 21

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. A-2 Lease Holsinger

Operator Jones, Shelburne Farmer Address Russell, Kans

Field \_\_\_\_\_ County Trego

Total Depth 3861 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 160' circulated with cement - 5 1/2" at 3857' with

125 sax cement behind - perforated at 3769'.

Filled with sand to 3750', set 4 sax cement with dump bailer,

pulled 2000' 5 1/2" - pumped hole full mud (40 sax Gel), pumped

cementing plug to 160', followed by 50 sax cement - cement

160 to 0'.

Mudding and cementing by Globe Cementing Co.

E. J. Lee  
District Conservation Agent

Date 6-13-56

JUN 14 1956

CONSERVATION DIVISION  
Wichita, Kan.

6-14-1956

PLUGGING  
FILE SEC 35 T 14 R 21 W  
BOOK PAGE 71 LINE 16