

15.195.30144.00.00

Form CP-3
Rev. 6-26-62

KANSAS

JP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
NOV 7 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Abercrombie Drilling, Incorporated,
Complete Address: 801 Union Center, Wichita, Kansas.
Lease Name Ethel Moore Well No. 1
Location CSE-SE-SE Sec. 26 Twp. 14 Rge. (E) (W) 21
County Graham *Trego* Total Depth 3883
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 4:45AM Day 2 Month 11 Year 1966

The Above well was plugged as follows:

275'--8 5/8" Surface pipe, cement circulated with 185 Sx. (6 3/4" hole)
Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.
cement thru DP. Heavy mud to 270', set plug and displaced 20 Sx. cement
thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

(Cementing operations performed by Sun Oil Well Cementing)

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Diebel*
Well Plugging Supervisor

INVOICED

DATE 11/8/66
INV. NO. 4244-W