

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company,

Complete Address: 1425 Wichita Plaza, Wichita, Kansas.

Lease Name Dinkel Well No. 1

Location NE-SW-NE Sec. 23 Twp. 14 Rge. (E) (W) 21

County Trego Total Depth 4010

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 9:15AM Day 12 Month 8 Year 1966

The Above well was plugged as follows:

237'--8 5/8" Surface pipe, cement circulated with 165 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 25 Sx.

cement thru DP. Heavy mud to 240', set plug and displaced 25 Sx, cement

thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx, cement

to bottom of cellar.

(Cementing operations performed by Globe Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Fehel  
Well Plugging Supervisor

DATE 8/15/66

INV. NO. 3748-11