

15.195.20135.00.00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,
Complete Address 370 West Wichita Ave., Russell, Kansas.
Lease Name Zonkger Well No. 1
Location NE-NE-NW Sec. 18 Twp. 14 Rge. (E) (W) 21
County Trego Total Depth 4130'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 5:00 PM Day 16 Month 9 Year 1969

The above well was plugged as follows:

169'--8 5/8" Surface casing, cement circulated with 120 Sx.
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pull DP to 750' and displaced 100 Sx. cement thru
DP from 750' to 425'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 125'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/19/69
INV. NO. 502-4

Signed: W. L. Nichols
Well Plugging Supervisor