

KANSAS

Form CP-3
Rev. 6-26-62STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Operator's Full Name Raymond Oil Company, Incorporated,Complete Address: 110 4th National Bank Building, Wichita, Kansas.Lease Name Kroeger Well No. 1Location NW-NE-SE Sec. 16 Twp. 11 Rge. (E) (W) 21County Trego Total Depth 4010Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company, Incorporated,Address: Box #405, Chase, Kansas License No. 436Operation Completed: Hour 6:00PM Day 16 Month 4 Year 1968

The Above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 185 Sx.
4008'--5 1/2" Production casing cemented with 125 Sx. Well plugged back to 3997'. No indication of perforations.Sanded well back to 3900' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well with 35 sacks gel using 5 sacks hulls in initial gel and followed with 130 Sx. cement. Maximum pump-in pressure--600#. Final shut-in pressure--425#.
(Mudding and cementing operations performed by Knight's pump truck) (Recovered 3207' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging SupervisorDATE 10/30/68
INV. NO. 8427-W

October 24, 1968

Re: Kroeger Well No. 1
NW NE SE Sec. 16-14S-21W
Trego County, Kansas

Mr. W. L. Nichols
P. O. Box 157
Morland, Kansas 67650

Dear Mr. Nichols:

We are herewith enclosing a copy of a well plugging record that we received October 23, 1968, from Raymond Oil Company regarding the plugging of the above captioned well. We received a well plugging application and driller's log requesting authority to plug this well April 1, 1968, and issued an authority that same date, however, we have checked our files and cannot find a report from you.

Please check this out and report to us at your earliest convenience.

Very truly yours,

J. Lewis Brock, Administrator

JLB:bb