

KANSAS

*sl*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Isern-Wells and E. A. Smith.

Complete Address Box #486, Ellinwood, Kansas.

Lease Name Wahlborg Well No. 1

Location NE-NE-SW Sec. 3 Twp. 14 Rge. (E) (W) 21

County Trego Total Depth 4080'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 10:00 AM Day 6 Month 11 Year 1971

The above well was plugged as follows:

197'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 100 Sx. cement thru  
DP from 750' to 425'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dicks*  
Well Plugging Supervisor

INVOICED

DATE 11-11-71

INV. NO. 4639-W