

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Mary Agnes Well No. 2

Location CN/2-NE-NE Sec. 24 Twp. 13 Rge. (E) (W)21

County Trego Total Depth 3951'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drilling, Incorporated,

Address Above License No. _____

Operation Completed: Hour 10:30 PM Day 8 Month 10 Year 1974

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 435'.

Circulated hole with heavy mud. Pulled DP to 660' and displaced 110 Cu. Ft. cement
thru DP from 660' to 335'. Pulled DP to 270' and displaced 30 Cu. Ft. cement thru
DP from 270' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/11/74

INV. NO. 92-W