

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1964

CONSERVATION DIVISION
Wichita, Kansas

8-31-1964

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling,

Complete Address: Victoria, Kansas.

Lease Name Tipton Well No. 1

Location NW-SW-NW Sec. 9 Twp. 13² Rge. (E) (W) 21

County Trego Total Depth 3986

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 5:00PM Day 26 Month 8 Year 1964

The Above well was plugged as follows:

~~182~~ 198'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx. cement thru DP.

Heavy mud to 180', set plug with 1/2 sack hulls and displaced 20 Sx. cement thru DP.

Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. D. Nichols
Well Plugging Supervisor

DATE 9/1/64

INV. NO. 9937-U