


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



WELL PLUGGING RECORD

Trego County. Sec. 33 Twp. 15S Rge. 25W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE SE

Lease Owner Robert M. Euwer

Lease Name Basinger Well No. 1

Office Address Suite 206, 110 No. Market, Wichita, Ks.

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed March 14, 1977

Application for plugging filed Verbal Application 19

Application for plugging approved Verbal Approval 19

Plugging commenced March 14, 1977

Plugging completed March 14, 1977

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation Depth to top Bottom Total Depth of Well 4452'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
4452'				8-5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,452 ft. (rotary total depth) to 800 ft. Set plug at 800 ft. and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 800 ft. to 250 ft. Set plug at 250 ft. and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 250 ft. to 40 ft. Set solid plug at 40 ft. and cemented with 10 sacks cement to cellar, 2 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4-1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing
Box 31, Russell, Kansas 67665

STATE OF Kansas

COUNTY OF Sedgwick

, ss.

Dean Britting, Agent (knowledge of owner)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Elsie Willison
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of March, 19 77

Elsie Willison - Notary Public.

My commission expires June 30, 1978



KANSAS GEOLOGICAL SOCIETY API NO. - 15-195-20,398.00
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Robert M. Euwer

SEC. 33 T. 15S R. 25W
LOC. SE SE

FARM Basinger


NO. 1

TOTAL DEPTH 4,452'
COMM. March 4, 1977
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED March 21, 1977

COMP. March 14, 1977

COUNTY Trego

KANSAS



CASING

20 10
15 8-5/8" 257' cemented w/225 sxs cement ELEVATION 2,445' KB.
12 6
13 5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS
Post Rock 50'
Shale and Lime 1,325'
Sand and Shale 1,619'
Shale 1,864'
Anhydrite 1,905'
Shale and Lime 2,765'
Lime and Shale 4,180'
Lime 4,310'
Lime and Shale 4,329'
Lime 4,385'
Lime and Shale 4,414'
Lime 4,452'
Rotary Total Depth 4,452'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas } ss:
County of Sedgwick }

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 21st. day
of March, 1977.

WILLIS
NOTARY

PUBLIC
NOTARY

My Commission Expires:

June 30, 1978

Elsie Willison
Elsie Willison - Notary Public