

15.195.20515.00.00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Trego SEC. 25 TWP. 15S RGE. 24W E/W  
Location as in quarters or footage from lines:

C NE SW


Lease Owner Kelso Casing Pulling

Lease Name Kislinger #1 Well No. \_\_\_\_\_

Office Address Box 176 Chase, Kansas 67524

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 12-24-81

Plugging completed 12-31-81

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4709'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	225'	none
				5-1/2"	4686'	2775'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3900' and set 5 sacks cement. Shot casing @3385', 3264', 3148' and 2993'. Pulled a total of 69 joints of pipe. Plugged well with 5 sacks hulls, 24 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.

RECEIVED  
STATE CORPORATION COMMISSION

1-14-1982

JAN 14 1982

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 82

My Commission expires:



Irene Hoover  
Notary Public.