

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Trego SEC. 18 TWP. 15S RGE. 24W E/W
Location as in quarters or footage from lines:
C SW/4

Lease Owner Kelso Casing Pulling
Lease Name Mollenkamp #1 Well No. _____
Office Address Box 176 Chase, Kansas 67524
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced XXXX 12-18-81
Plugging completed 12-31-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ bottom T.D. 4801'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	219'	none
				5-1/2"	4800'	2959'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4725' and set 5 sacks cement. Shot pipe @3592',
3482', 3357', 3226', 3102' and 2976'. Pulled a total of 93 joints of pipe. Plugged
well with 5 sacks hulls, 27 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc.
Plugging Completed.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling RECEIVED 1-14-1982
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or owner or operator of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1982

My Commission expires:



Irene Hoover
Notary Public.

Schlumberger

BOREHOLE COMPENSATED
SONIC LOG

COUNTY TREGO FIELD WILDCAT LOCATION 13-15S-24W WELL MOLLENKAMP #1 COMPANY PLAINS RESOURCES	COMPANY PLAINS RESOURCES INC.,			
	AND W.B.C.O.			
	WELL MOLLENKAMP #1			
	FIELD WILDCAT			
COUNTY TREGO		STATE KANSAS		
LOCATION C SW/4		Other Services: FDC-CNL-GR DLL-MSFL-GR RFT		
API SERIAL NO	SEC	TWP	RANGE	
	18	15S	24W	
Permanent Datum: GROUND LEVEL		Elev.: 2473		
Log Measured From KB		5 Ft. Above Perm. Datum		
Drilling Measured From KB		Elev.: K.B. 2478 D.F. ---- G.L. 2473		
Date	12-3-78			
Run No.	ONE			
Depth-Driller	4800			
Depth-Logger (Schl.)	4801			
Btm. Log Interval.	4798			
Top Log Interval	212			
Casing-Driller	8 5/8 @ 210 @			
Casing-Logger	212 @			
Bit Size	7 7/8			
Type Fluid in Hole	STARCH			
Dens.	Visc.	10 49		
pH	Fluid Loss	6.8 6.0 ml	ml ml ml ml	
Source of Sample	FLOWLINE			
Rm @ Meas. Temp.	240 @ 60 °F @ °F @ °F @ °F			
Rmf @ Meas. Temp.	175 @ 60 °F @ °F @ °F @ °F			
Rmc @ Meas. Temp.	--- @ --- °F @ °F @ °F @ °F			
Source: Rmf	Rmc	--- ---		
Rm @ BHT	150 @ 103 °F @ °F @ °F @ °F			
TIME	Circulation Stopped	12/2-2100		
	Logger on Bottom	12/3-0500		
	Max. Rec. Temp.	103 °F °F °F °F		
	Equip.	Location	7747 WICH	
	Recorded By	GRIFFIN		
	Witnessed By Mr.	LAYMAN		

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1981

CONSERVATION DIVISION
Wichita, Kansas