


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 36 Twp. 15S Rge. 21W (E) (W)
Location as "NE/CNW/SW" or footage from lines. NE NE NE
Lease Owner Don E. Pratt, et al
Lease Name North Well No. A1
Office Address Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 22 1956
Application for plugging filed Enclosed 19
Application for plugging approved September 22, 1956
Plugging commenced September 22, 1956
Plugging completed September 22, 1956
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty
Producing formation Depth to top Bottom Total Depth of Well 1428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 575' plug, 1/2 sack hulls and 20 sax cement; filled to 40' with mud, set plug, 1/2 sack of hulls and 10 sax cement.

10-2-1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Golden Cat Drilling Company
Address Box 775, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Trego, ss.
W. E. Wickizer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. E. Wickizer*
WaKeeney, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of September, 1956

My commission expires Sept. 10, 1959
Joy H. Horak Notary Public

PLUGGING
FILE SEC. 36 T. 15 R. 21W
BOOK PAGE 103 LINE 10

STATE OF KANSAS

INVOICE

September 27, 19~~56~~

To: _____
Don E. Pratt

Box 656

Hays, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: _____ ASSESSMENT AS FOLLOWS:

PLUGGING

D. K. North "A" # 1
NE NE NE 36-15-21W
Trego County
File No. 103-10

\$ 25.00

NOTE: We also need a well plugging application, well log, and a well plugging record on this well to complete our file.

*Pa.
Ch # 1548
C - 16
10-2-56
E.W.S.*

RETURN THIS COPY WITH REMITTANCE



GOLDEN CAT DRILLING

and 15.195.00145.00.00

SERVICING COMPANY

Office Phone 379

Residence Phone 350

P. O. Box 611

To Kansas Well Log Bureau
508 East Murdock
Wichita, Kansas

Well North A1 (NE NE NE) Sec. 36 Tw. 15S R. 21W Co. Trego

Commenced: September 5, 1956

Completed: September 22, 1956

Total Depth: 4428'

Set 590' 8 5/8" surface pipe

0 to 590	Clay, post rock and shale
590 895	Shale and shells
895 1175	Shale and sand
1175 1510	Red bed
1510 1637	Shale and shells
1637 1679	Anhydrite
1679 2160	Shale and shells
2160 2290	Shale and salt
2290 2515	Shale and lime
2515 2690	Lime and shale
2690 2755	Lime, shale and pyrite
2755 2875	Lime
2875 2895	Sandy lime
2895 3355	Lime and shale
3355 3621	Lime and shale
3621 3795	Lime and shale
3795 3908	Lime
3908 4085	Lime
4085 4102	Lime and shale
4102 4154	Cherty lime
4154 4164	Lime and Shale
4164 4194	Sand
4194 4243	Cherty cong. and sand
4243 4287	Lime and shale
4287 4428	Lime and chert

4428 TD

PLUGGING
 FILE SEC. 36 T. 15 R. 21W
 BOOK PAGE 103 LINE 10

W. E. Wickizer
 W. E. Wickizer
 Notary Public

Subscribed & Sworn to before me this 26th day of September, 1956

My Commission Expires: Oct 1, 1959