


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Driller Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 29 Twp. 15 Rge. 21 (E) W (W)
Location as "NE/CNW&SW" or footage from lines NW NW NE
Lease Owner W. E. Wickizer
Lease Name Kutina Well No. A1
Office Address Box 775, WaKeeney, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 10 19 56
Application for plugging filed October 10 19 56
Application for plugging approved October 10 19 56
Plugging commenced October 10 19 56
Plugging completed October 10 19 56
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set @ 220 w/ 1/2 hulls 15 sacks cement, top plug set @ 40' w/ 1/2 hulls 10 sacks cement, filled hole w/ mud to 220'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Golden Cat Drilling Company
Address Box 775, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Trego, ss.
W. E. Wickizer (employee of owner) or (owner & operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
WaKeeney, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 56

[Signature]
Notary Public

My commission expires 7-12-60

PLUGGING
FILE SEC 29 T. 15 R. 21W
BOOK PAGE 107 LINE 30

OCT 22 1956
CONSERVATION DIVISION
Wichita, Kansas

10-22-1956

Invoice No. _____

15.195.00138.00.00

WaKeeney, Kansas, 10-10-56

GOLDEN CAT DRILLING and SERVICING COMPANY

Office Phone 379

Residence Phone 350

P. O. Box 611

To Kansas Well Log Bureau
508 East Murdock
Wichita, Kansas

Well Kutina "A1" (NW NW NE) Sec. 29 Tw. 15 R. 21W Co. Trego

Total Depth: 4365'

Commenced: September 24, 1956

Completed: October 10, 1956

Set 227' 8/5/8" surface pipe

0	to	40	Surface clay and gravel
40		195	Sand and post rock
195		345	Shale
345		540	Sand and shale
540		780	Sand
780		1050	Shale and shells
1050		1500	Sand, shale and pyrite
1500		1605	Red bed and shells
1605		1727	Red bed and shells
1727		1755	Anhydrite
1755		2095	Shale and shells
2095		2258	Shale, lime and pyrite
2258		2425	Shale and lime
2425		2615	Lime and shale
2615		2655	Lime
2655		2745	Lime and shale
2745		2830	Lime, shale and pyrite
2830		2903	Lime, shale and chert
2903		2920	Shale and lime
2920		2935	Sand
2935		3165	Shale and lime
3165		3280	Lime and shale
3280		3875	Shale and lime
3875		3990	Lime
3990		4020	Lime and shale
4020		4073	Lime
4073		4148	Lime and shale
4148		4164	Cherty lime
4164		4182	Chert
4182		4201	Chert and lime
4201		4243	Lime and chert
4243		4314	Conglomerate
4314		4321	Conglomerate and sand
4321		4365	Chert

4365 TD

RECEIVED
OPERATION COMMISSION
OCT 22 1956

PLUGGING RESERVATION DIVISION
Wichita, Kansas
FILE SEC. 29 T. 15 R. 21W
BOOK PAGE 107 LINE 30

W. E. Wickizer
W. E. Wickizer