

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Trego County, Sec. 16 Twp. 15S Rge. 21 (EX) (W)

Location as "NE/CNW/SW" or footage from lines. NW NE SE
Lease Owner Mull Drilling Company, Inc.
Lease Name Gaschler Well No. 1
Office Address 1625 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed March 11 19 65
Application for plugging filed March 11 19 65
Application for plugging approved March 11 19 65
Plugging commenced March 11 19 65
Plugging completed March 11 19 65
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4170' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	312'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spot 20 sx @ 550'
20 sx @ 300'. Hulls-
Plug 10 sx A 40'.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1965
4-26-1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of March, 1965.

My commission expires 5-22-66

Jean Kollar
Notary Public.

15.195.30008.00.00

DRILLERS LOG

Gaschler No. 1

CASING RECORD:
8 5/8" @ 312'
w/225 ex cement

COMPANY: Mull Drilling Co.
CONTRACTOR: Red Tiger Drilling Co.
COMMENCED: March 2, 1965
COMPLETED: March 10, 1965

DESCRIPTION:
NW NE SE
16-158-21W
Trego Co., Kans.
ELEVATION: 2228 DF
2231 RB

TOTAL DEPTH: 4170'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, clay & rock	0	75	
Shale & Shells	75	313	
Shale	313	854	
Sand	854	882	
Shale & Redbed	882	940	
Shale & Shells	940	1015	
Sand Streaks	1015	1245	
Redbed	1245	1580	
Anhydrite	1580	1629	
Shale & Shells	1629	1835	
Shale	1835	2200	
Lime & Shale	2200	3625	
Heebner Shale	3625	3629	
Lime	3629	3980	
Shale & Lime	3980	4030	
Lime	4030	4065	
Shale & Lime	4065	4104	
S.D.	4104	4165	
Lime	4165	4170	

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1965
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 12th day of March, 1965.

Jean Hollas
Notary Public

My Commission Expires:

5-22-66