

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	SEC. 10		

Locate well correctly on above
Section Plat

TREGO County. Sec. 10 Twp. 15s Rge. 21 (E) (W)
 Location as "NE/CNW/SW" or footage from lines APP. NE NW SW
 Lease Owner PETROLEUM, INC.,
 Lease Name PRICE 'E' Well No. 1
 Office Address R.R. #2, GREAT BEND, KANSAS
 Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
 Date well completed JANUARY 6 19 67
 Application for plugging filed JANUARY 6 19 67
 Application for plugging approved JANUARY 6 19 67
 Plugging commenced JANUARY 6 19 67
 Plugging completed JANUARY 6 19 67
 Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4230 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	540	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUD TO 480', FOLLOWED BY WOODEN PLUG, PLACED 25 SACKS CEMENT ON TOP OF PLUG.
 MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACKS HULLS AND 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
 Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.

MONTE CHADD (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD DIST. PROD. SUPT.

(Signature) *Monte Chadd*

(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of JANUARY, 19 67

My commission expires MAY 28, 1969

Richard H. Dumbler
Notary Public.

WELL LOG

COMPANY Petroleum, Incorporated

SEC. 10 T. 15S R. 21W

FARM Price

NO. E-1

LOC. NE NW SW


TOTAL DEPTH 4230'

COUNTY Trego

COMM. 12-26-66

COMP. 1-6-67

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 540' w/375 sx

ELEVATION 2241' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 45' Post Rock
- 120' Sand and Shells
- 220' Blue Shale
- 540' Shale
- 870' Shale and Shells
- 920' Sand
- 1240' Shale, Shells, Sand and Red Bed
- 1320' Sand
- 1595' Shale and Shells
- 1620' Anhydrite
- 1625' Shale
- 1795' Shale and Shells
- 2220' Shale
- 2410' Shale with Lime
- 2700' Lime and Shale
- 3220' Shale and Lime
- 3400' Shale and Shells
- 3495' Shale and Lime
- 3685' Lime and Shale
- 3764' Lime
- 3826' Lime and Shale
- 4230' Lime
- 4230' RTD

RECEIVED
 STATE CONSERVATION COMMISSION
 JAN 18 1967
 CONSERVATION DIVISION
 TOPEKA, KANSAS

State of Kansas }
 County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Price No. E-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 11th day of January 19 67

My Commission Expires: May 28, 1969

Richard H. Trumbler
 NOTARY PUBLIC