


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



C NE SW SW Trego County, Sec. 1 Twp. 15S Rge. (E) 21(W)  
Location as "NE/CNW/SW" or footage from lines C NE SW SW  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name Tom Moore Well No. #1  
Office Address 801 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed January 2 19 66  
Application for plugging filed Verbally - January 1 19 66  
Application for plugging approved Verbally - January 1 19 66  
Plugging commenced January 1 19 66  
Plugging completed 5:30 A.M., January 2 19 66  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbally

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2870 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with rotary mud, and dumped in 100 sacks common cement.  
Shut in at 5:30 a.m., January 2, 1966.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 7 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Mildred Saxton (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mildred Saxton  
801 Union Center Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 66

My commission expires June 16, 1967

Leah Faye Hefke  
Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Abercrombie Drilling, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 FARM: Moore #1  
 LOCATION: NE SW SW, Sec. 1-15S-21W  
 Trego County, Kansas  
 COMMENCED: December 21, 1965  
 COMPLETED: January 2, 1966

0	-244	Post Rock & Clay Shale
244	430	Shale & Shells
430	680	Sand & Pyrite
680	830	Shale
830	1047	Sand
1047	1356	Shale
1356	1395	Anhydrite
1395	1610	Sand & Shale
1610	1954	Shale & Shells
1954	2285	Lime & Shale
2285	2443	Shale & Lime
2443	2910	Lime & Shale
2910	3198	Shale & Lime
3198	3342	Lime & Shale
3342	3516	Lime
3516	3551	Lime & Chert
3551	3835	Lime
3835	3870	Lime & Shale
3870		Rotary Total Depth

Set 8 5/8" surface casing at 233' with 185 sx cement with 3% C.C.L.

DRY AND ABANDONED

TOPS: (Electric Log)

ELEVATION: 2049' K. B.

Anhydrite (driller)	1356-1395
Heebner	3368' (-1319)
Toronto	3393' (-1344)
Lansing	3413' (-1364)
Cherokee Shale	3802' (-1753)
Arbuckle	3854' (-1805)
Total Depth	3870' (-1821)

**RECEIVED**  
 STATE CORPORATION COMMISSION

JAN 7 1966

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Mildred Saxton, do hereby certify that the above and foregoing is a true and correct copy of the log of the Moore #1, NE SW SW, Section 1-15S-21W, Trego County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

*Mildred Saxton*  
 Mildred Saxton, Secretary

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this sixth day of January, 1966.

*Leah Faye HeFke*  
 Leah Faye HeFke, Notary Public

My commission expires June 16, 1967