

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Billing Building  
Wichita, Kansas

R-21W  
NORTH

	1		

Locate well correctly on above  
Section Plat

Trego County. Sec. 1 Twp. 15 Rge. 21 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 1500' from West line & 2310' from north  
Lease Owner Deep Rock Oil Corporation  
Lease Name T. Moore "A" Well No. 1 line  
Office Address Box 1051, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 11 19 53  
Application for plugging filed August 11 19 53  
Application for plugging approved August 11 19 53  
Plugging commenced August 11 19 53  
Plugging completed August 11 19 53  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, approval from Mr. Eldon Petty obtained prior to plugging.

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Dry Hole Depth to top Bottom Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 220'. Set HOWCO wood plug at 220' and mixed and pumped in 35 sacks of regular bulk cement. Filled to 30' with heavy mud and set HOWCO wood plug. Mixed and pumped in 15 sacks regular cement to top of pipe and into cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. Rine Drilling Company  
Address 320 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. Walker*


Box 1146, Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of August, 19 53

My commission expires September 28, 1955

23-8390-s 6-51-20M

*W. L. Walker*  
Notary Public.



AUG 25 1953  
CONSERVATION DIVISION  
Wichita, Kansas  
8-25-1953

15.195.00043.00.00



# DEEP ROCK OIL CORPORATION

ATLAS LIFE BUILDING  
TULSA 2, OKLAHOMA

August 27, 1953

Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Gentlemen:

Enclosed is well log for our T. Moore "A" Well No. 1,  
located in SE SE NW, Section 1-15S-21W, Trego County, Kansas.


Yours very truly,

A handwritten signature in cursive script that reads "Jack Smith".

Jack Smith  
Kansas Production Superintendent  
Box 1146  
Hutchinson, Kansas

CD:aw

RECEIVED  
STATE CORPORATION COMMISSION



T. Moore "A" Well No. 1  
 SE SE NW  
 Sec. 1-15S-21W  
 Trego County, Kansas

Contractor: The R.W. Rine Drilling Company  
 Started: 7-30-53      Finished: 8-11-53

Log

Sand & Sand Rock	0	-	30
Surface Clay & Shale	30	-	160
Shale & Shells	160	-	250
Sand, Shale & Shells	250	-	750
Shale	750	-	775
Sand, Shale & Red Bed	775	-	1375
Anhydrite	1375	-	1415
Shale & Shells	1415	-	2040
Shale & some Lime	2040	-	2300
Lime & Shale	2300	-	2410
Lime	2400	-	2505
Lime-Shale-Sand (Trace of Iron Pyrite)	2505	-	2695
Lime & Shale	2695	-	2950
Lime	2950	-	3063
Lime & Shale	3063	-	3375
Lime	3375	-	3465
Lime & Shale	3465	-	3515
Lime	3515	-	3638
Lime & Shale	3638	-	3744
Chert & Lime	3744	-	3782
Cherty Lime & Sand	3782	-	3804
Sand, Lime & Shale	3804	-	3834
Chert & Lime	3834	-	3884
Lime	3884	-	3900
Total Depth			3900

RECEIVED  
 STATE CORPORATION COMMISSION

**PLUGGING**  
 FILE SEC. 1-15S-21W  
 ROCK PAGE 121 LINE 39

STATE OF KANSAS

# INVOICE

To: \_\_\_\_\_ 19\_\_\_\_  
 August 19 53  
 \_\_\_\_\_  
 Deep Rock Oil Corporation  
 \_\_\_\_\_  
 Box 1146  
 \_\_\_\_\_  
 Hutchinson, Kansas

STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 800 BITTING BUILDING  
 WICHITA, KANSAS

FOR: \_\_\_\_\_ ASSESSMENT AS FOLLOWS:  
 PLUGGING

T. Moore "A" Well No. 1  
 SW SE NW 1-15-21W  
 Trego County  
 File No. 121-39

25.00

**COPY**

**A F E** 1427  
 pd. ck # 70106  
 8-29-53  
 C.B.



NOTE: We also need a well log and a well plugging record to complete our files.

**RETURN THIS COPY WITH REMITTANCE**



## DEEP ROCK OIL CORPORATION, P. O. BOX 1051, TULSA 2, OKLAHOMA

DR-482-B

VOUCHER NO.	DESCRIPTION	GROSS AMOUNT	NET AMOUNT
8-843-26 27	8/20/53 STATEMENT 8/19/53 STATEMENT		25.00 <u>25.00</u> 50.00