

State of Kansas



15.195.20303.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Mary Agnes Well No. 2.

Location: CN/2-NE-NE Sec. 24 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 3951' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

2 7/8" -- 8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 435'.

Circulate hole with heavy mud. Pull DP to 660' and displace 110 Cu. Ft. cement thru DP. Pull DP to 270' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols

Conservation Division Agent