

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 26 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Leonard Williams of Vaughan Drilling, Inc., has this

date requested permission to plug the following described well:

Mr. Williams guarantees payment of the plugging fee.

Operator's full Name: Don Thompson

Complete Address: P. O. Box #296, Burlington, Colorado.

Lease Name: Thorne Well No. 1

Location: CSE-NW Sec. 1 Twp. 12 Rge. (E)(W)22

County: Trego Total Depth 4095' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Williams was instructed to plug the well as follows:

183'--8 5/8" Surface pipe, cement circulated with 125 Sx.

Dakota section from 775' to 950'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. B. Nichols

Conservation Division Agent