

State of Kansas



15.195.30158.00.00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1966

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

12-19-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Herb Mason of Dunne & Gardner Drlg Co. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: W. R. Gross & Dunne & Gardner Petroleum,

Complete Address: 300 Schweiter Building, Wichita, Kansas.

Lease Name: Helget Well No. 1

Location: CNW-SW Sec. 35 Twp. 12 Rge. (E)(W) 21

County Trego Total Depth 3885 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

130' -- 8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulate hole with heavy mud, set plug @ 600' and 25 Sx. cement.

" " 120' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

N. L. Finkel

Conservation Division Agent