

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 19 1963

CONSERVATION DIVISION
 Wichita, Kansas

8-19-1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. George Galloway of Mayfield & Smith Drilling has this

date requested permission to plug the following described well:

Mr. Galloway guarantees payment of the plugging fee.

Operator's full Name: Mayfield & Smith Drilling Incorporated,

Complete Address: 928 Union Center, Wichita, Kansas.

Lease Name: Garrett Well No. 1

Location: CSE-SW Sec. 16 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 4070 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Galloway was instructed to plug the well as follows:

- 208' -- 8 5/8" Surface pipe, cement circulated.
- Circulate hole with heavy mud, set plug @ 600' and 20 Sx cement.
- " " 190' with 1/4 Sk hulls & 20 Sx cement.
- " " 40' with 1/2 Sk. hulls & 10 Sx cement.

Very truly yours,

K. S. Spichals
 Conservation Division Agent