



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Johnny Crowe of Garvey Drilling Company has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Walz Well No. C-1

Location: SE-SW-SE Sec. 11 Twp. 11 Rge. (E)(W) 21

County: Trego Total Depth 3809' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

182'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 575'.

Circulate hole with heavy mud. Pull DP to 800' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent