

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Merle Herring of Barnes & Sons Pipe Pulling has this
date requested permission to plug the following described well:
Messman-Rinehart Oil Co.
Mr. Herring guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company,
Complete Address: 518 Petroleum Building, Wichita, Kansas.
Lease Name: Kelsch Well No. 1
Location: NE-NE-NE Sec. 2 Twp. 12 Rge. (E) (W) 22
County Trego Total Depth 4110 Oil Well X
Gas Well Input Well SWD Well D & A Lost Hole

Mr. Herring was instructed to plug the well as follows:
1015'--10 3/4" Surface pipe, cement circulated. 4110'--5 1/2"
production casing cemented with 50 Sx. Well plugged back to
3670'. Top perforations @ 3649'.

Sand well back to 3630' and set 5 Sx. cement with dump bailer.
Pull 5 1/2", bail hole to 375', set rock bridge and fill hole to
bottom of cellar with Redi-Mix cement.

Very truly yours,

H. L. Nichols