

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 21 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Inc. has this

date requested permission to plug the following described well:

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Co. Inc.

Complete Address: P. O. Box 787, Great Bend, Kansas

Lease Name: Newcomb Well No. # 1

Location: N/2 NW NE Sec. 5 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3592 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Finch was instructed to plug the well as follows:

210' of 8 5/8" surface pipe, cement circulated with 225

sacks. 3591' of 4 1/2" long string, cemented with 150 sacks.

Plugged back to 3442'. Perferated 3420' to 3423'. Sand to

3400', cement with 3 sacks. Fill hole with mud to 205',

10' rock bridge, cement with 20 sacks. Fill hole with mud

to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent