

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 195-20-834.00.00

Operator's Full Name Beren Corp.

Complete Address 970. Fourth. Financial Center. Wichita, Ks.

Lease Name Leroy Well No. # 1

Location N/2-N/2-SE- Sec. 17 Twp. 11 Rge. 21 (East) (West)

County Trego. Total Depth 3813

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pioneer Drilling Co.

Address 308. W. Mill Plainville Ks. License No. _____

Operation Completed: Hour: 2:30 AM Day: 4 Month: July Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

KB. 2205. DT. 1500' And. 1639. SP. 317' 7.8 5/8" cwc. 200 sk.
Cir. Mud 10 min @ 940' Pumped down. Drilled to
60. 9x cem. 5/50 Per 60' @ 900'
40 " " 320' Built Bridge To 40'
10. " " 40' too.
5. " " in Rathok

By Sum.

RECEIVED
 STATE CORPORATION COMMISSION
 8-7-1981
 AUG 7 1981

I hereby certify that the above well was plugged as herein stated.

DATE 9-25-81

Signed: [Signature]
 Conservation Division Agent

INV. NO. 7496W

CONSERVATION DIVISION
 Wichita Kansas

15.195.20834.00.00

WELL LOG

OPERATOR: Beren Corporation

WELL NAME: Leroy #1 LOCATION: N/2 N/2 SE 14-11S-21W

COUNTY: Trego STATE: Kansas

WELL COMMENCED: July 23, 1981 WELL COMPLETED: August 4, 1981

ELEVATION: 2205' K.B. TOTAL DEPTH: 3813'

PRODUCTION: D & A RIG NO: # 3

CASING - 8 5/8": 8 Jts new 24# tallied at 317.61' set @ 324.61' cemented with 200 sxs
60-40 pos 2% gel 3%cc P.D. @ 3:30 P.M. 7-24-81 did circ.
5 1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	325'	sand and shale	325' - 1 degree	
325'	850'	sand and shale		
850'	1324'	shale and sand		
1324'	1629'	red bed shale		
1629'	1640'	anhydrite		
1640'	1683'	anhydrite		
1683'	1909'	shale	1909' - 2 1/2 degree	
1909'	2335'	shale		
2335'	2530'	shale and lime		
2530'	2658'	shale and lime	2622' - 2 degree	
2658'	2865'	shale and lime		
2865'	3065'	shale and lime		
3065'	3234'	shale and lime		
3234'	3344'	shale and lime		
3344'	3425'	shale and lime		
3425'	3516'	shale and lime		
3516'	3525'		3525' - 2 1/2 degree	
3525'	3536'	lime and shale		
3536'	3575'	lime and shale	3575' - 1 1/2 degree	
3575'	3582'	shales and sand		
3582'	3654'	lime and shale		
3654'	3667'	lime	3667' - 2 degree	
3667'	3684'	shale and lime		
3684'	3754'	lime and shale		
3754'	3787'	shale and lime		
3787'	3793'	lime and shale		
3793'	3798'	limes		
3798'	3803'	lime		
3803'	3813'	lime		

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1981
CONSERVATION DIVISION
Wichita, Kansas

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By Stacy A. Milgros

SUBSCRIBED AND SWORN TO, BEFORE ME, This 18th day of August, 1981

Sharon Garvert
NOTARY PUBLIC

