

15.195.20194.00.00

Form CP-3
Rev. 6-4-68

KANSAS

Al STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Walz Well No. C-1

Location SE-SW-SE Sec. 11 Twp. 11 Rge. (E) (W) 21

County Trego Total Depth 3809'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Box #1164, Great Bend, Kansas. License No.

Operation Completed: Hour 9:00 AM Day 10 Month 9 Year 1971

The above well was plugged as follows:

182'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement thru
DP from 800' to 475'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. S. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9-14-71
INV. NO. 4328-4