

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NE SW

SEC. 3 TWP. 11 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 8 A-1 Lease Kroeger

Operator Theodore Gore Address Wichita, Kans

Field _____ County Trego

Total Depth 3745 Feet.

Plugging Contractor Empire Drg Co & Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 208' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

600', displaced 20 sax cement through drill pipe, heavv mud to

200', set cementing plug, displaced 20 sax cement through drill pipe,

heavy mud to 40', set cementing plug. 1/2 sack hulls and 10 sax cement

to bottom cellar.

Cementing by Globe Cementing Co.

District Conservation Agent

Date 10-11-57

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1957
CONSERVATION DIVISION
Wichita, Kansas

10-15-1957

PLUGGING
FILE SEC. 3 T. 11 R. 21
BOOK PAGE 53 LINE 35