

15.195.00236.00.01

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 3 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name Webb Well No. 1

Location NE-NE-SE Sec. 2 Twp. 11 Rge. (E) (W) 21

County Trego Total Depth 3733

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Glenn and Smith Pipe Pulling Company,

Address: 204 East 6th, Ellinwood, Kansas. License No. 396

Operation Completed: Hour 5:00PM Day 27 Month 12 Year 1965

The Above well was plugged as follows:

180' -- 8 5/8" Surface pipe, cement circulated.

3733' -- 5 1/2" Production casing cemented with 125 Sx. Top perforation @ 3444'.

Sanded well back to 3430' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" to 580' and circulated heavy gel mud (used 16 sx. gel),

pulled 5 1/2" to 520' and displaced 20 Sx. cement thru 5 1/2". Pulled

5 1/2" to 180' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set  
bridge @ 35' and 10 Sx. cement to bottom of cellar.

(Recovered 2565' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 1/4/66

INV. NO. 2543-W