


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated.

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Augustine Well No. B-1

Location 150' So. of NE-NE-NW Sec. 21 Twp. 14 Rge. (E) (W) 21

County Trego Total Depth 3982'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 1:30 PM Day 17 Month 10 Year 1968

The Above well was plugged as follows:

154'--8 5/8" Surface casing, cement circulated with 115 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement thru
DP from 800' to 475'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from 180'
to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10/21/68
INV. NO. 8666-4