

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTRECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1964

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Messman-Rinehart Oil Company.

Complete Address: 518 Petroleum Building, Wichita, Kansas.

Lease Name Kelsch Well No. 1

Location NE-NE-NE Sec. 2 Twp. 12 Rge. (E) (W) 22

County Trego Total Depth 4110

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 4:00PM Day 13 Month 3 Year 1964

The Above well, was plugged as follows:

1015'--10 3/4" Surface pipe, cement circulated. 4110'--5 1/2" production casing cemented with 50 Sx. Well plugged back to 3670', Top perforations @ 3649'.

Sanded well back to 3630' and set 5 Sx cement with dump bailer.

Pulled 5 1/2", found top of fluid @ 375', set wood and rock bridge and

filled hole to bottom of cellar with Redi-Mix cement. used 7 1/2 yards.

(Recovered 2860' of 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols  
Well Plugging SupervisorDATE 3/18/64INV. NO. 8802-11