

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Co.

Complete Address 217 N. Water Wichita, Ks 67202

Lease Name Newcombe Heirs Well No. 1-V

Location NW/SW/NE Sec. 5 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3724

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks 67524 License No. 436

Operation Completed: Hour 4:00 PM Day 13 Month 3 Year 1970

The above well was plugged as follows:

770 ft of 8 5/8 circulated with cement. 3505 ft of 4 1/2 long string
cemented with 150 sacks. Plug back to 3486 ft. Top perf. 3332 ft.
5 sacks cement with bailer. 2800 ft of 4 1/2 pulled. Mud to 250 ft. ,
10 ft rock bridge, 25 sacks cement. Mud to 30 ft, 10 ft rock
bridge, 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Bilerstein
Well Plugging Supervisor

DATE 3/19/70
INV. NO. 1605-U