

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1966

CONSERVATION DIVISION
WICHITA, KANSAS

8-17-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Texaco, Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name Newcombe Heirs Well No. # 1

Location SE SE NE Sec. 5 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3560'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 4:00PM Day 15th Month August Year 1966

The Above well was plugged as follows:

221' of 8 5/8" surface pipe, cement circulated. 3542' of 4 1/2" long string,
cemented with 60 sacks. This is an open hole. Bottom of the hole was
sanded to 3214', and cemented with 3 sacks, through the dump bailer.
Hole was flowing with water, and a squeeze job was necessary. 10 sacks
of Gel-Mud and 75 sacks of cement was pumped in the surface pipe, through
an 8 5/8" swage, to a pressure of 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audine Elving
Well Plugging Supervisor

DATE 8/17/66

INV. NO. 3796-4