

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 21 1963

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name Chief Drilling Co. Inc.Complete Address: P. O. Box 787, Great Bend, KansasLease Name Newcomb Well No. # 1Location N/2 NW NE Sec. 5 Twp. 21 Rge. 13 (E) (W) WCounty Stafford Total Depth 3592Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers Inc.Address: 1809 Lakin, Great Bend, Kansas License No. 462Operation Completed: Hour 8:00AM Day 16th Month May Year 1963

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cement circulated with 225 sacks. 3591' of  
4 1/2" long string, cemented with 150 sacks. Plugged back to 3442'. Perfer-  
ated 3420' to 3423'. Sanded to 3400', cemented with 3 sacks. Fluid was up  
in hole. Plug was set at 205', with a 10' rock bridge, cemented with 3 sacks  
of Cal-Seal, let set over night. Next morning fluid would not bail down.  
A squeeze job was necessary. 10 sacks mud and 60 sacks cement was pumped  
in to pipe through 8 5/8" swage. Next morning cement was down to 40' in  
pipe, 10' rock bridge, cemented with 10 sacks to base cellar  
2817' of 4 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**DATE 5/21/63INV. NO. 9090-WSigned: Archie Elving  
Well Plugging Supervisor