

15-009-22618-00-00

LEASE NAME Jacobs

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

4290 Ft. from S Section L

330 Ft. from E Section L

SEC. 32 TWP. 16 RGE. 12 (E) or W

COUNTY Barton

Date Well Completed 2-11-82

Plugging Commenced 10-26-94

Plugging Completed 10-26-94

LEASE OPERATOR D. R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400, Wichita, Ks.

67202

PHONE# (316) 263-8237 OPERATORS LICENSE NO. 5427

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 10-26-94 (date)

by Mr. Hubert Deines (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Arbuckle Depth to Top 3334 Bottom 3342 T.D. 3342

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	295	none
				5 1/2"	3334	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each

Allied pumped 50 sacks 60-40 pozmix 10% gel, 50# hulls down surface pipe. Max. pressure 900. shut-in pressure 600. Pumped 250 sacks 60-40 pozmix 10% gel down 5 1/2" w/450# hulls. Max pressure 900. shut-in pressure 600. Holes were perforated 850', 450' and 300'. 10-30-94 Cement went down 400' from surface. Dumped 4 yards ready-mix to bring cement to surface. -Plugging complete.

Name of Plugging Contractor none License No. \_\_\_\_\_

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D. R. Lauck Oil Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Melvin G. Urban

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Melvin G. Urban

(Address) P. O. Box 488, Ellinwood, Ks. 67526

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 94

Renee L. Bock  
Notary Public

My Commission Expires: 5-25-97

USE ONLY ONE SIDE OF EACH FORM



RECEIVED  
OIL CORPORATION COMMISSION  
NOV 14 1994  
WICHITA, KANSAS

Form 1  
Revised 01

15-009-22618-00-00

D. R. Lauck Oil Company, Inc. - Jacobs #2  
221 S. Broadway, Suite 400 SE NE NE Sec. 32-16S-12W  
Wichita, Kansas 67202 Barton County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: December 16, 1981  
Completed: January 14, 1982

Drillers Log

Blue Shale	510
Red Bed	774
Anhydrite	800
Shale & Shells	2030
Shale	2380
Shale & Shells	2730
Shale & Lime	2965
Shale	3010
Shale & Lime	3155
Lime & Shale	3275
Lime & Chert	3342 RTD

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1994  
CONSERVATION  
WICHITA, KANSAS