

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Department Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,797.0000

LEASE NAME Grow

WELL NUMBER #3

3570 Ft. from S Section Line

3716 Ft. from E Section Line

SEC. 28 TWP. 21 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 1-26-89

Plugging Completed 2-1-89

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE# (316-792-1922) OPERATORS LICENSE NO. 6588

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 31, 1989 (date)

by Paul Luthi and Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3716'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	290'	None
				5-1/2"	3713'	2,936.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3540' and 5 sacks cement. Shot casing at 3200' & 2900'. Pulled 89 joints of 5-1/2" casing. B.J. Titan plugged well with 350# hulls, 10 sacks gel, 50 sacks cement 10 sacks gel, 50# hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 650 psi and shut in 400 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1989

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

Iona M. Leatherman
Notary Public

My Commission Expires: