

15.185.20821.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 28 Twp. 21S Rge. 12 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW SE SE

Lease Owner Icer Addis
Lease Name Greenwalt Well No. 1
Office Address P. O. Drawer 8038, Wichita, Kansas 67208
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed May 20, 19 78
Application for plugging filed May 20, 19 78
Application for plugging approved May 20, 19 78
Plugging commenced May 20, 19 78
Plugging completed May 20, 19 78
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 3670
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	249'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug 540' w/40 sx.
2nd plug 240' w/40 sx.
3rd plug 40' w/12 sx.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1978
5-24-1978
CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Iannitti Drilling Company

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
K. T. Woodman (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

K. T. Woodman
1008 Douglas Bldg., 104 S. Broadway,
(Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 78

My commission expires Feb. 11, 1980

Justina Chamberlain
Notary Public.



15.185.20821.0000

K. F. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

May 22, 1978

Company;	Icer Addis
Fram;	#1 Greenwalt
Location;	NW SE SE
Section;	28-21S-12W
County;	Stafford
Total Depth;	3670'
Comm;	May 13, 1978
Compl;	May 20, 1978
Contractor;	Woodman & Iannitti Drilling Co.
Casing;	8 5/8 @ 249' w/200 sx.
Production;	D & A

Figures Indicate Bottom Of Formations:

20	Shale & Sand
253	Sand & Shale
633	Redbed & Shale
646	Shale
671	Anhy
1420	Shale
1854	Shale & Lime
2200	Lime & Shale
2330	Lime w/Shale Streaks
2555	Shale & Lime
2977	Lime & Shale
3019	Lime & Shale
3168	Lime
3450	Lime
3518	Lime
3605	Lime, Shale & Cherty
3636	Shale
3670	Arbuckle

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1978
CONSERVATION DIVISION
Wichita, Kansas

Woodman & Iannitti Drilling Co.
K. F. Woodman
K. F. Woodman