

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
500 Blitting Building
Wichita, Kansas

OR

Strike out upper line
when reporting plugging
of formations.

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 28 Twp. 21 Rge. (E) 12 (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines Center S 1/2 St SE
Lease Owner G. W. Keyes Drilling Company et al
Lease Name Ziegenbusch Well No. 1
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Small Well abandoned as dry
Date well completed Nov. 19, 1945
Application for plugging filed Oct. 13, 1947
Application for plugging approved Oct. 13, 1947
Plugging commenced Oct. 14, 1947
Plugging completed Oct. 26, 1947
Reason for abandonment of well or producing formation non-commercial well

If a producing well is abandoned, date of last production April 30 1945
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herb Kerr
Producing formation Simpson Depth to top 3574 Bottom ----- Total Depth of Well 3664 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe		0	259	10 3/4	259	0
Oil String		0	3390	7"	3390	1736'
Liner		3250	3606	5 1/2	356	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented bottom of hole with 4sacks, mudded back to 260 feet. Set rock bridge at 260 feet and cemented with 20 sacks on top of bridge. Filled with mud to 15'. Set rock bridge at 15' and cemented with 10 sacks on top of bridge, cement returning to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Keyes Drilling Company
Address Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
I, G. W. Keyes, part owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *G. W. Keyes*
Ellinwood, Kansas (Address) 11-21-47

SUBSCRIBED AND SWORN to before me this 18th day of November, 1947.
George A. Meyer
Notary Public.

My commission expires February 10, 1951

PLUGGING
FILE SEC 28 T 21 R 17W
BOOK PAGE 143 LINE 74

WELL LOG

G. W. Keyes Drilling Company, Owner - Ziegenbusch #1
 C Half SE SE Section 28, Township 21 S, Range 12 W
 Stafford County, Kansas

Figures indicate bottom of formation

	0	to	220	Sand
			260	Red bed
			647	Red bed
			680	Anhydrite
			1150	Red bed and shale
Elevation	1854		1255	Shale and shells
			1480	Salt, shale and shells
			1580	Shale and shells
Pipe:			1670	Lime
			1825	Broken lime
10 3/8" set at 259'			1900	Shale and shells
7" set at 3300'			2210	Broken lime
5 1/2" set at 3569'			2535	Shale and shells
			2600	Shale
			2635	Lime
Tops:			2745	Broken lime
			3200	Lime
Anhydrite	647		3230	Shale
Lansing	3276		3300	Broken lime
Simpson	3574		3390	Lime
Arbuckle	3603			
			3390	Total Rotary Depth

Started August 10, 1945
 Rotary work completed August
 23, 1945

Cable Tools

3407	Lime
3411	Shale
3421	Lime
	Show of oil 3414 - 3420
3466	Lime
3468	Shale
3474	Lime
3476	Shale
3521	Lime
3524	Red shale
3527	Shale
3534	Red bed
3540	Shale
3557	Simpson
3567	Simpson, shale and lime
3571	Green shale and lime
3574	Lime
3581	Simpson
3664	Lime
3664	Total Depth

State of Kansas)
 County of Barton) ss

I, G. W. Keyes, Part Owner of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed and that the same are true and correct.

Subscribed and Sworn to before me this 15th day of February, 1946.

G. W. Keyes

J. J. Rader

 Notary Public

My commission expires July 7, 1948.

PLUGGING

FILE SEC 28 T 21 R 17 W

BOOK PAGE 143 LINE 74