

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittin Building  
Wichita, Kansas

Stafford County, Sec. 28 Twp. 21S Rge. ~~12~~ 12 (W)

Location as "NE/CNW&SW¼" or footage from lines C-NE-SE-NE

Lease Owner Sunray Oil Corporation

Lease Name Ziegenbusch Well No. 2

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 20 19 54

Application for plugging filed June 21 19 54

Application for plugging approved June 22 19 54

Plugging commenced June 20 19 54

Plugging completed June 20 19 54

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3630 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3133		8 5/8	330	none
Toronto		3154				
Douglas		3167				
Iatan		3270				
Lansing-KC	water	3279	3515			
Conglomerate	water	3527				
Arbuckle	water	3616	3630			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole from 3630' to 330' and ran 35 sax cement. Mudded hole to 40' and ran 10 sax cement. Dry hole plugged and abandoned.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company  
Address Philtower Building, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.  
Robert K. Crouch (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch  
Box 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 19 54

My commission expires December 24, 1956

Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1954  
CONSERVATION DIVISION

PLUGGING  
FILE NO. 287 2 R 120  
BOOK PAGE 42 LINE 34

6-29-1954

15.185.12188.0000

Sunray Oil Corporation  
Tulsa, Oklahoma

Tulsa, Oklahoma  
June 24, 1954

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: June 10, 1954  
Drilling Completed: June 20, 1954

Ziegenbusch #2 NE/4 Sec.  
28-21S-12W, Stafford  
County, Kansas.

DRILLERS LOG

Sand	0-150
Red Bed Sand	150-250
Red Bed, Shale & Shells	250-330
Red Bed	330-600
Hard Sand	600-680
Shale	680-845
Shale & Lime	845-1350
Shale & Shells	1350-1450
Lime & Shale	1450-1595
Lime	1595-1790
Lime & Shale	1790-1915
Lime	1915-2265
Sand & Shale	2265-2389
Shale & Lime	2389-2855
Lime & Shale	2855-2990
Lime	2990-3103
Sandy Lime & Shale	3103-3215
Lime & Shale	3215-3310
Lime	3310-3412
Lime & Shale	3412-3422
Lime	3422-3527
Cherty Lime	3527-3576
Sand & Lime	3576-3630 TD

I, Fred E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Oil Corporation's Ziegenbusch #2 NE/4 Section 28-21S-12W, Stafford County, Kansas.

*Fred E. Stickle*  
Fred E. Stickle

*Lillian T. Bonham*  
Notary Public

February 13, 1956

My Commission Expires

PLUGGING  
WELL NO. 28-21-12W  
PAGE 42 LINE 31

RECEIVED  
CONS...  
WILLI...