

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas

Lease Name Walker Well No. # 1

Location NW SW SW Sec. 33 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3641

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 14th Month April Year 1964

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cemented with 175 sacks. 3637' of 5 1/2"
long string, cemented with 100 sacks. Bottom of the hole was sanded
to 3630', and cemented with 5 sacks. Fluid was up in the hole. Plug
was set at 260', bridged with 10' of rock. 1 sack of Cal-Seal was
mixed in barrel and put on plug through the dump bailer, and let set
for 2 hours. Hole bailed down, and 25 sacks cement was added to the
plug. Hole was filled with mud to 40', 10' rock bridge, and cemented
with 10 sacks to base cellar. 3020' of 5 1/2" long string was recovered
from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/16/64
INV. NO. 8964-W