

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 147-14

LOCATION NE-NE-~~25E~~^{SW}

SEC. 23 TWP. 21 RGE. 12W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease A. Walker

Operator Standard Oil & Gas Co. Address Box #7 - Ellinwood, Kans.

Field _____ County Stafford

Total Depth 3625 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 256 ft. Circulated with cement,
7 casing at 3618 - Plugged back to 3440 ft with
cement & Chert - Dumped 6 sacks of cement at 3440 ft
Shot off & pulled the 7 casing - Filled with mud
& 256 ft - Back Bridged & 10 sacks of cement at 256 ft.
Mud to 30 ft - Plug & 10 sacks of cement
at the surface

Pipe Pulling, Inc. - Plugging Contractor

RECEIVED

Conservation Div.
MAY 26 1950
STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 35 T 21 R 12W
BOOK PAGE 147 LINE 14

C. M. Stough
District Conservation Agent

Date 4-14-50