

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-NE-NE

SEC. 33 TWP. 11 RGE. 11-4

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Sittner

Operator Artroll Company Address 700 West Monroe Chicago Ill.

Field _____ County Stafford

Total Depth 2615 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 1/2" - 230 ft. Circulated with cement.
7" casing set at 3355 ft. - 5/8" casing set at 3525 ft.
Plugged back to 3603 ft. with cement. Filled hole
with sand to 3575 ft. - Dumped 4 sacks of cement at 3575 ft.
Shot off & hulled the 5/8" casing - Set Bridge & 5 sacks
of cement at 3340 ft. Shot off & hulled the 7" casing -
run to 230 ft. Set Rock Bridge & 20 sacks of cement
at 230 ft. - run to 20 ft. Bridge & 10 sacks of cement
at the surface.

STATE OF KAN.

FEB 29 1952

CONC...

C. W. Stough
District Conservation Agent

Date 2-19-52

PLUGGING
FILE SEC. 33 T. 21 R. 11-4
BOOK PAGE 142 LINE 29