

15-009-06627-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-SW

SEC. 25 TWP. 16 RGE. 12-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Oeser

Operator Thornay & Harton Oil Co. Address Hairington - Kans.

Field _____ County Barton

Total Depth 3338 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 147 ft. Circulated with cement.
4 1/2" casing set at 3330 ft. - 100 sacks of cement.
Plugged back with sand to 3320 ft. - Dumped
15 sacks of cement at 3320 ft. - Shot off & pulled
the 4 1/2" casing - mud to 250 ft. Set rock bridge.
20 sacks of cement at 250 ft. - mud to 35 ft. -
Plug & 10 sacks of cement at the surface.

RECEIVED
STATE CORPORATION COMMISSION

01-08-53 JAN 8 - 1953

C. H. Stough
District Conservation Agent

Wichita, Kansas Date 1-5-53

PLUGGING
SEC 25 TWP 16 RGE 12
PAGE 71 LINE 11