

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-20921-00-01  
Spot: NWSENWNW Sec/Twnshp/Rge: 26-13S-30W  
4271 feet from S Section Line, 4387 feet from E Section Line  
Lease Name: WESLEY Well #: 1  
County: GOVE Total Vertical Depth: 4588 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2557		135 SX
SURF	8.625	313		200 SX

Well Type: SWD UIC Docket No: D25101.0 Date/Time to Plug: 07/24/2017 12:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: CHUCK TONER Company: FALCON EXPLORATION, INC. DBA Phone: (620) 546-4752

Proposed Plugging Method: Ordered 455 sx 60/40 pozmix 4% gel cement w/500 # hulls  
Perforations at 1158'.  
Squeezed with 300 sx cement to complete Alt II

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/24/2017 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perforated at 1894' and 2048'. Ran tubing to 1912' and pumped 30 sx neat cement followed by 70 sx cement w/300 # hulls. Well went on vacuum. Pulled 1000' of tubing and let set for one hour. Ran tubing in to 1912' and pumped 275 sx cement w/250 # hulls. Cement circulated. Pulled tubing out and topped off with 30 sx cement. Pressured to 200 psi.

GPS: 38.89980 -100.62742

Perfs:

Top	Bot	Thru	Comments
1894	2048		


Remarks: GLOBAL CEMENT TICKET # 3056

Plugged through: TBG

KCC WICHITA  
AUG 24 2017  
RECEIVED  
INVOICED  
AUG 30 2017

District: 04

Signed

  
(TECHNICIAN)

CM

JUL 27 2017