

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-00488-00-01
Spot: SWSWSWNE Sec/Twnshp/Rgc: 25-31S-33W
2770 feet from S Section Line, 2487 feet from E Section Line
Lease Name: BECKER Well #: 1
County: SEWARD Total Vertical Depth: 2718 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1202		
PROD	5.5	2690	0	WITH 800 SX CMT
SURF	8.625	597		WITH 400 SX CMT

Well Type: SWD UIC Docket No: D27455.0 Date/Time to Plug: 08/09/2017 4:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: 1. MIRUSU, set CIBP @ 1200' to cover perms. 2. Run tbg to 1200' & spot 60 sx cmt., no hulls to cover the csg leak @ 759-780'. 3. Pull tbg to 600' & circ cmt to surface w/ approx. 60 sx & 100# hulls in last 40 sx to shut off csg leak. 4. TOOH & top off 5 1/2" casing. 5. Fill annulus w/ cmt. 6. RDSU, cut and cap well 4' below ground.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/09/2017 9:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

SET CIBP @ 1202'. 1ST PLUG AT 1200' WITH 60 SX CMT. 2ND PLUG AT 550' WITH 100 SX CMT & 100# HULLS. CHECK BACKSIDE WITH 14 SX CMT TO 500 PSI.

Top	Bot	Thru	Comments
1250	1310		


Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBC

INVOICED
AUG 31 2017

District: 01

Signed



(TECHNICIAN)

SA

RECEIVED
AUG 18 2017
KCC DODGE CITY