

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-01012-00-01
Spot: SENWNWNE Sec/Twnshp/Rge: 15-25S-9W
4688 feet from S Section Line, 1996 feet from E Section Line
Lease Name: ARCHIE B Well #: 3-15
County: RENO Total Vertical Depth: 4900 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>3911</u>	PROD	5.5	4345	1582	175 SX
Op Name: <u>RAMA OPERATING CO., INC.</u>	SURF	8.625	207		200 SX
Address: <u>101 S MAIN ST</u> <u>STAFFORD, KS 67578</u>					

Well Type: SWD UIC Docket No: D26334.0 Date/Time to Plug: 05/25/2010 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RANDY G Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 05/25/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP AT 4300', SPOTTED 2 SX ON TOP. SHOT CASING OFF AT 1582'. PULLED CASING TO 1390' SPOTTED 50 SX OF COMMON 4% CC. PULLED CASING TO 798'. TAGGED TOP OF BOTTOM PLUG WITH SANDLINE AT 1250' PUMPED 35 SKS OF COMMON. PULLED CASING TO 360', CIRCULATED TO SURFACE WITH 195 SX OF 60/40 4% GEL.

Perfs:

Top	Bot	Thru	Comments
4345	4900		

INVOICED
SEP 01 2017

Remarks: BASIC ENERGY PROVIDED CEMENT FOR THIS JOB. NO AGREEMENT WITH LANDOWNER, NO LEASE.

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)