

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19589-00-01
Spot: NWSENEW Sec/Twnshp/Rge: 8-25S-5E
4463 feet from S Section Line, 3263 feet from E Section Line
Lease Name: WILSON A Well #: 218
County: BUTLER Total Vertical Depth: 964 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	964		
PKR		901		PACKER TYPE AND SETTING DEPTH: BAKER AD-1 @ 901 (POOH)
PROD	4.5	964		115 SX
SURF	6.625	1994		70 SX
TI	2.375	901		POOH

Well Type: EOR UIC Docket No: E27410.4 Date/Time to Plug: 08/06/2017 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 08/16/2017 1:50 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH WITH TUBING @ 950', QES ESTABLISHED CIRCULATION MIXED & PUMPED 65 SXS 60/40 POZMIX 4% GEL 2% CC W/HULLS TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, SWEDGED INTO CASING, PUMPED 15 SXS 60/40 POZMIX 4% GEL 2% CC. SIP 300#. QES CEMENT TICKET #53434. TOTAL 80 SXS 60/40 POZMIX 4% GEL 2% CC.

Perfs:

Top	Bot	Thru	Comments
938	958	CSG	

Remarks: WELL CEMENTED ON BACKSIDE 252'0". FAILED MIT

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

INVOICED
SEP 0-1-2017

18