

1 080544

15.185.30000.0000

Docket No. C-11,568
completion date: 12/11/64

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE SW NE SEC. 2, T 21 S, R 11 W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F. G. Holl
Name & Address: 6427 East Kellogg
Wichita, KS 67207

Lease Name Rugan Well # D-4
County Stafford 118.20
Well Total Depth 3637 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 15 Month: 8 Year: 1986

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3460' Open hole 3460' to 3637' Elevation 1760 K.B. Anhydrite 456'

1st plug sand back to 3400' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls and 100 sx cement with 2 sx hull mix

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 15 Month: 8 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls and 2 sx hulls mixed with 100 sx cement-light.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Recovered 2800' 4 1/2" casing. Used A.I.C. cement by Allied.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 8-20-86

Paul A. Luthi
8-20-86 signed

J. A. [Signature]
(TECHNICIAN)

INV. NO. 14777

AUG 20 1986